

Feed-Forward / Feedback required

Ralph J. Steinhagen


**Accelerators & Beams Department, CERN
and 3rd Physics Institute, RWTH Aachen**

- stabilisation of key beam parameters:
 - Orbit, Energy, Tune, Chromaticity and Coupling

- Stage I operation (43x43 bunches)
 - Summary of requirements
 - Summary of expected drifts
 - Requirements for feedbacks

- Not covered:
 - Control of higher multipoles (b_4 , b_5 , ...)
 - Luminosity
 - Fast transverse feedback (→ W. Höfle)
 - Details on instrumentation (BPMs, BBQ, Q-PLL, ...)
 - Providers session on Tuesday

Preliminary Remark:



■ Requirements and time-line of key beam parameters control depend on:

1. Capability to control level/ tolerances of particle losses in the machine

- Machine protection & Collimation
- Quench prevention

2. Commissioning efficiency

3. Operational efficiency: optimisation of (integrated) luminosity
4. ...

→ requirements on Orbit, Energy, Tune and Chromaticity scale rather with total beam intensity and beam energy than with stages.


- Example: Collimation System, Phase I: 43x43 → $N_{max} \approx 5 \cdot 10^{12}$ protons/beam

- required collimation inefficiency^{1,2}:

$$\eta = \frac{\tau_{min} \cdot R_q \cdot L_{dil.}}{N_{max}}$$

- Min. accept. lifetime: $T_{min} \approx 10$ min.
- Dilution length: $L_{dil} \approx 50$ m
- Quench level (@7 TeV) R_q : $R_q \approx 7.6 \cdot 10^6$ prot./m/s

→ $\eta < 0.05$ (\approx single stage system)



- Distinction global/local less obvious, expected injection aperture (arc) $\sim 7.5 \sigma$ → local requirements \approx global requirements³
- Many more less strict requirements → see additional slides for details: machine protection, [minimisation of feed-down effects](#), beam instrumentation, [..]
- Orbit stability of $< 1 \sigma$ sufficient for ≤ 43 bunches !?**
- Nominal: $\approx 0.3 \sigma$ locally (collimation) and $\sim 0.3 \sigma$ globally (machine protection³, preserving scrubbing efficiency, ..)

¹ R. Assmann, "Collimation and Cleaning: Could this limit the LHC Performance?", Chamonix XII, 2003

² S. Redaelli, "LHC aperture and commissioning of the Collimation System", Chamonix XIV, 2005

³ R. Steinhagen, "Closed Orbit and Protection", MPWG #53, 2005-12-16

- Energy matching between of SPS → LHC
 - horizontal orbit corrector magnets adjust LHC energy
 - residual non dispersion orbit perturbation needs further correction (e.g. → orbit FB)
- A priori not urgently required for low intensity beams, but
 - may keep capture losses below an acceptable limit
 - minimises abort gap population & feed-down of higher multipoles

→ favourable once running with high intensity

- Required¹ initial momentum stability: $\Delta p/p < 1 \cdot 10^{-4}$
 - Simplifies setup of nominal beam after commissioning pilot
- Nominal²: $\Delta p/p < 1 \cdot 10^{-4}$

¹ E. Chapochnikova, private communications

² E. Shaposhnikova, “Abort Gap Cleaning and the RF System”, Chamonix XII, 2003

³ T. Linnecar, “RF Capture and Synchronisation”, Chamonix XII, 2003

Requirements on Tune and Chromaticity

- Tune spread $\Delta Q|_{av} \approx 1.15 \cdot 10^{-2}$
 - fixed by available space in Q-diagram
 - Working assumption: (first order: no non-linear effects, avoid 3rd and 4th order resonances)

$$\delta Q \leq 0.015 \rightarrow 0.003$$

(early commissioning $\rightarrow 43 \times 43$)


- Nominal^{1,2}: $\Delta Q \leq 0.003$ (inj.) $\delta Q \leq 0.001$ (coll.)

Chromaticity

- SPS: $\Delta p/p: 2.8 \cdot 10^{-4}$
(actual $\Delta p/p$ given by SPS \rightarrow LHC inj.)
- \rightarrow allowed max lin. chromaticity (5-6 σ , first order):

$$Q'_{max} \propto \frac{\Delta Q_{av}}{\Delta p/p} \rightarrow Q'_{max} \approx 10 \text{ \& } Q' > 0!$$

- Nominal^{1,2}: $Q'_{max} \approx 2 \pm 1$




"Numbers are estimates, other more/less strict choices are of course possible – commissioning will clarify real requirements!"

¹ S. Fartoukh, O. Brüning, "Field Quality Specification for the LHC Main Dipole Magnets", LHC Project Report 501

² S. Fartoukh, J.P. Koutchouk, "On the Measurement of the Tunes, [...] in LHC", LHC-B-ES-0009, EDMS# 463763

- Minimum distance Δ between tunes given by coupling c
 - LHC injection: $\Delta = |q_x - q_y| = 0.03$, collision: $\Delta = 0.01$



- Closest tune approach $\rightarrow c \ll 0.03$ and $c \ll 0.01$ respectively
- Requirement for other feedbacks that rely on decoupled planes
- Proposal for alternate higher tune split¹: $\Delta = 0.1$ ($q_x = 0.285$, $q_y = 0.385$)

¹S. Fartoukh, "Commissioning tunes to bootstrap the LHC", LCC #31, 2002-10-23

Expected Dynamic Perturbations vs. Requirements

- From Decay/Snap-back **expected dynamic perturbations*** (MB & MQ)
 - For details, please see additional slides

	Orbit [σ]	Tune [$0.5 \cdot f_{rev}$]	Chroma. [units]	Energy [$\Delta p/p$]	Coupling [c_]
Exp. Perturbations:	~ 0.5	0.014 (0.06)	~ 70 (140)	$\pm 1.5e-4$	~ 0.01 (0.1)
Pilot bunch	-	± 0.1	+ 10 ??	-	-
Stage I Requirements	$\pm \sim 1$	$\pm 0.015 \rightarrow 0.003$	$> 0 \pm 10$	$\pm 1e-4$	$\ll 0.03$
Nominal	$\pm 0.3 / 0.5$	$\pm 0.003 / \pm 0.001$	$1-2 \pm 1$	$\pm 1e-4$	$\ll 0.01$



- Chromaticity is the most critical parameter to control**
 - defines lifetime and dynamic aperture (= losses) inside the ring
 - Tune is less critical but its measurement a pre-requirement for above
- Require coupling control esp. at start of ramp to enable other controls**
- Control of orbit is the easiest one**
 - Measurement and correction scheme well established
 - consequence of having BPM with 100k turn acquisition: \rightarrow Energy feedback
- Stage I: injection more relaxed (except Chromaticity)**

* numbers in brackets are 'worst case'

Expected Time-Scales of Perturbations

Orbit & Energy:

- Injection (ground-motion, Δb_1): $\sim 0.4 \sigma/10 \text{ h}$ \rightarrow Control @1 Hz sufficient
- Snap-back: $0.3 \sigma/100 \text{ s}$ \rightarrow Control @1-10 Hz ??
- β^* -Squeeze: $0.1 \sigma/s$ \rightarrow Control @10++ Hz OK




- $(\Delta Q'/\Delta t)_{\text{max}} < 1.3 \text{ units/s}$ & $(\Delta Q')_{\text{max}} < \sim 10 \text{ units}$
 \rightarrow (measure &) control chromaticity every $\approx 10 \text{ seconds}$ (or faster)

Parameter control, either through...

- Feed-Forward: (FF)**
 - Steer parameter using precise process model and disturbance prediction
 - mostly using magnet model predictions based on magnet measurements
 - The (only) choice for the sector test and very first LHC injection
- Feedback: (FB)**
 - Steering using rough process model and measurement of parameter
 - Two types: within-cycle (repetition $\Delta t \ll 10$ hours) or cycle-to-cycle ($\Delta t > 10$ hours)

preferred choice!



- From the steering point of view: \rightarrow All control schemes possible (see Massimo's talk)
- Choice of Feedback vs. Feed-forward
 - depends on available robust beam parameter measurements

- In principle: → Work of an operator = manual feedback!
 - (Semi)-automated FB → liberates operators/EIC for more important tasks
 - Expected LHC turn around time is long (hours)
 - Trial-and-Error optimising/learning of “injection, ramp, squeeze...” may
 - potentially cause quenches (→ further delays)
 - will delay total commissioning till first collisions

- Experiences during LEP commissioning, Engineers In Charge (EIC¹):
 - “Many beams lost during ramp due to absence of Orbit & Tune feedback”
 - un-anticipated movement of low-beta quadrupoles....
 - Let's learn from EIC experience:
 - Establish parameter measurement and feedbacks at an early stage!

¹J. Wenninger, M. Lamont, M. Jonker, G. Roy, P. Collier, H. Burkhardt, ...

- Most advanced feedback¹, main “clients”: Collimation & Machine Protection
- Measurement^{2,3} and correction scheme well established
 - successful SPS Prototype⁴
 - BPM available from early startup (required for threading the beam!)
 - Does not necessarily require LHC wide BPM/COD synchronisation (slow timing)
 - Either self-triggered @ 1-2 Hz or semi-automatic steering program (coded!)
 - For-free: minimises dynamic feed-downs due to moving orbit
(e.g. moving orbit in sextupoles and coupling, many other snap-back related effects)
- Proposed baseline should and can be used at an early stage (circulating beam)
→ latest before ramping
- nominal performance (bandwidth $f_{bw} \approx 1\text{Hz}$, $\Delta x < 0.2 \sigma$) requires:
 - slow timing and beta-beat <20%, coupling is an issue


¹ J. Wenninger, “LHC Orbit Feedback Specification”, available on request

² E.B. Holzer: “BDI Commitments and Major Issues for Individual Instrumentation” (this workshop)

³ H. Schmickler: “Running in the Diagnostics”, Chamonix XIII

⁴ R. Steinhausen, “LHC Orbit Stabilisation Tests at the SPS”, PAC05 & CERN-AB-2005-052

- Injection oscillation to estimate injection mismatch $(\Delta p/p)_{inj}$



$$\left(\frac{\Delta p}{p}\right)_{inj} = \frac{\sum_i^N D_i \cdot \Delta x_i}{\sum_i^N D_i^2}$$

local dispersion: D_i
 average over
 $N \approx 300$ arc monitors

- Robust measurement: BPM systematics on Δx_i and D_i cancel!
 - “no” high-precision calibration required
 - Moderate turn-by-turn acquisition $\Delta x \approx 200 \mu\text{m}$ (pilot) @ ~ 300 arc monitors
 - $\Delta p/p$ resolution $\approx \text{few } 10^{-6} \rightarrow$ sufficient for nominal operation! (COD hysteresis $\rightarrow \Delta p/p \approx 6 \cdot 10^{-7}$)
- Horizontal arc corrector dipole magnets used to adjust LHC energy


- Later: Tide compensation (FF or FB possible) to optimise (preserve) aperture
- Minimal requirements for stage I:
 - BPMs:
 - BST (Beam synchronous timing) to trigger on injection of individual batch
 - Turn-by-turn acquisition should not affect (block) orbit acquisition
 - Orbit correction (FB) required to minimise non-dispersion orbit (2nd order effect)
 - someone who actually implements the algorithm in the front-end
- Could be used at an early stage (circulating beam)
 - latest before RF capture losses become an issue

- Traditional tune measurement method: kick and 'BPM 100k turn' acquisition
 - Emittance blow-up, not ideal for continuous feedback
 - Kick is an issue w.r.t. machine protection and collimation:
 - Collimation $\Delta x_{\max} < 0.3 \sigma$ vs. desired kick $\Delta x_{\min} > 1\text{mm} \sim 1 \sigma$
 - scrapes the beam!
 - move collimator out → require dedicated low intensity runs
 - worse BPM performance & cycle-to-cycle reproducibility issues
 - backup solution on day 0: comes for free while threading the beam¹!
 - New method (BI baseline): Base-Band-Q Meter (BBQ)
 - Can measure tune without (or very small) excitation and resolution in the 10^{-4} range
 - Phase Lock Loop to enhances S/N ratio of tune signal
 - 0.1 - 10 μm level excitation (depending on beam noise level) → negligible ϵ -blow up
 - Q-kicker rate limit: PLL-tune measurement @ $< 2 \text{ Hz}$ → sufficient for Stage I
- The candidate for feedback use!

¹ J. Wenninger, "Quadrupole Error Localization using Response Fits", LHC-OP #38, 2005-05-08

Tune and Chromaticity Feedback II/III

- Base-Band-Q Meter¹ (BBQ) available from day 0-1 (see R. Jones' talk on Tue.)
- Issues: Potential locking on
 - Synchrotron side bands, however: predicted error $\delta Q \sim 0.005 \rightarrow$ maybe OK for Phase I ?
 - Multiple of mains (50 Hz) signal, error $\delta Q \sim 0.002 \rightarrow$ OK for Phase I ?
 - **H/V-coupling** (issue @ HERA \rightarrow “BLL” and RHIC) & coupled bunch modes²
 - **Coupling control: pre-requirement for safe tune feedback during ramp**



¹ M. Gasior, R. Jones, “The Principle and First Results of Betatron Tune Measurement [...]”, LHC Proj. Rep. 853

² S. Fartoukh, J.P. Koutchouk, “On the Measurement of the Tunes, [...] in LHC”, LHC-B-ES-0009, EDMS# 463763

- Day 0 - workhorse: Classic approach

- Slow $\Delta p/p$ modulation and tune tracking:

$$Q' \propto \frac{\Delta Q}{\Delta p/p}$$

- Method used in LEP → proven & robust¹

- Requires moderate radio-frequency changes ($\Delta p/p \sim 10^{-4}$) and tune tracking

- similar issues as tune feedback

- May be enough to cope with snap-back and ramp induced b_3 drifts

(at least during Phase I)

- Day N - new approach: Head-Tail-Chromaticity

- Presently requires large kicks (ϵ blow-up, machine protection issues)

- envisaged to move to a BBQ similar principle

- continuous Q' measurement without notable ϵ blow-up

- Requires time for commissioning and may be not available on 'day 0'!

- Experiences from RHIC¹:
 - Coupling during ramp breaks tune (and other) feedbacks
 - potential quick-fixes: “no/stop feedbacks” during ramp



- PLL Coupling measurement exists² (R. Jones):
 - Info on unperturbed tunes Q_x and Q_y - ideal for tune FB
 - Measures coupling amplitude $|C|$ as well as its phase locally
 - real-time data at the same rate as tune data

- Common FB “Chicken-Egg-Problem”:

- Measurement breakdown due to uncontrolled coupling/chroma.
- Feedback control breakdown due to failing measurement

My proposed solution: **Control coupling (& chroma) before its measurement becomes an issue**


Tune-PLL & coupling measurement scheme:



¹P. Cameron et al.: “Advances towards the measurement and control of LHC Tune and Chromaticity”, DIPAC’05

²R. Jones, P. Cameron, Y. Luo, “Towards a Robust Phase Locked Loop Tune Feedback System”, Brookhaven Nat. Lab., C-A/AP/#204, May 2005,

- Tune and coupling measurement @ RHIC (will use FB this year!):



- control strategy - ideas exist but require more analysis:

- Feedback might work assuming coupling due to many distributed sources (global optimisation)
- Coupling feedback not easy, hope to gain from RHIC experience

- Should have coupling feedback at an early stage (preferably before ramping)

- Which feedback first:
 - Coupling correction is a pre-requirement for FBs during ramp
 - Orbit: easiest to implement but not most important
 - Chromaticity: most important but not easiest feedback (requires tune!)
 - Energy FB is a logical consequence having a 100k turn acquisition
 - Tune FB is a logical consequence having a Q-meter (-PLL)
- Feedback priority list: Tune → Chromaticity → Orbit → Energy
- Feedback list of “what's easiest to commission”:
 - 1st: Orbit → functional BPM system → OK
 - 1½: Energy → consequence of 100k turn acquisition → OK
 - 2nd: Tune → functional Q-meter (-PLL) → SOSO
 - 3rd: Chromaticity → functional Q-meter and $\Delta f/f$ modulation → ??
- Foresee time to commission feedbacks at an early stage
 - Most instruments can be commissioned parasitically with first circulating beam
 - Foresee semi-automatic control (measure→correct) implementations (poorman's feedbacks)
 - Investment now (!!) will help later with and save time while ramping the beam

- Parameter stability requirements and perturbation predictions:
 - Need automated control of: Energy, Orbit, Tune, Chromaticity and Coupling
 - requirements scale rather with total beam intensity and beam energy

- Feedback are most useful and efficient at an early commissioning stage
 - Cope well with random effects and machine uncertainties
 - Parameter measurement is an issue
 - BPM system available at 'day 0' → no problem for orbit and energy feedback
 - Tune, Chromaticity and Coupling are more difficult

- Two reasons to use feedbacks at an early stage:
 1. Give EICs, operators, ... the time to take care of more important things
 2. Without control of coupling and chromaticity, Q/Q' measurements become an issue

- ~~Santa-Claus~~ Early LHC wish-list: operational PLL + coupling measurement
 - Tune and Q' feedback with $\Delta f/f$ modulation as a workhorse



Reserve Slides

- Current decay in main bends^{1,2} (b_1 & b_3) and lattice quadrupoles (b_2):

	Main Dipoles			MQ	
	Δb_1	Δa_1	Δa_2	Δb_2	
Decay/Snap-back	0.78 ± 0.72	-0.75 ± 2.61	-0.01 ± 0.22	1.64 ± 0.42	1.68 ± 0.56

- ...LHC injection optics (v6.5, MAD-X)

- Orbit (H/V): $\Delta x \approx 0.28 \cdot \sigma \cdot \Delta b_1(R) \rightarrow \Delta x(y) \sim 0.2 \sigma$
- Energy: $\Delta p/p \approx 10^{-4} \cdot \Delta b_1(S) + \text{tides} \rightarrow \Delta p/p \sim 1.3 \cdot 10^{-4}$
- Tune(MQ): $\Delta Q_{x(y)} \approx 8 \cdot 10^{-3} \cdot \Delta b_2(S) \rightarrow \Delta Q \sim 0.014$
- Chromaticity: $\Delta Q'_{x(y)} \approx 44(-39) \cdot \Delta b_3(S) \rightarrow \Delta Q' \sim 62 - 70$
- Coupling: $\Delta c_- \approx 0.46 \cdot \Delta a_2(S) \rightarrow \Delta c_- \sim 0.005$
- Coupling: $\Delta c_- \approx 0.014 \cdot \Delta a_2(R) \rightarrow \Delta c_- \sim 0.003$

- + feed-downs of higher multipoles, energy, orbit ... depend on operational conditions

- Tune³ $\Delta Q_{x(y)} \approx 0.06$
- Coupling⁴ $\Delta c_- \approx 0.1$ (worst case)

- However it is unclear (lots of non-evident assumptions): static \leftrightarrow dynamic components

\rightarrow commissioning will show

- Machine intrinsic effects: Squeeze (raw uncorrected orbit drift ~ 30 mm)
- Environmental sources & machine element failures (ground motion, girder, cryogenics, ...)

¹L. Bottura, "Cold Test Results: Field Aspects", Proceedings of Chamonix XII, 2003

²L. Bottura, "Superconducting Magnets on Day 1", Proceedings of Chamonix XI, 2002

³S. Fartoukh, J.P. Koutchouk, "On the Measurement of the Tunes, [...] in LHC", LHC-B-ES-0009, EDMS# 463763

⁴S. Fartoukh, "Commissioning tunes to bootstrap the LHC", LCC #31, 2002-10-23



Dynamic Perturbations vs. Requirements Summary


Exp. Perturbations:		Orbit [σ]	Tune [$0.5 \cdot f_{rev}$]	Chroma. [units]	Energy [$\Delta p/p$]	tau
Inj. Energy mismatch		0.25	0.0017	~ 1.3	1.0E-4	sev. days
Moon/Sun Tides ¹		0.14	0.0009	~ 1.2	5.0E-5	~ 10 hours
Random Ground Motion ²		0.3 – 0.5	-	-	-	~ 10 hours
Decay/Snapback ³	$b_1 \approx 0.75$	0.11	0.0030		7.5E-5	$\sim 1200/100$ s
	b_2 & b_3	0.03	-	$\sim 70 - 140$	-	
	MQ: $b_2 \approx 1.7$		0.014			
Ramp induced* ³	$b_1 \approx 1.50$	0.22	0.0019	~ 8	1.5E-4	Start of ramp
MCB Hysteresis ⁴		0.01	-	-	Xx	
MCB/PC stability ⁵	± 7 mA/60A GeV	0.1	-	-		
β^* Squeeze	0.5 mm misalign.	~ 30 mm	??	??	-	~ 1200 s

*assuming lin. Ramp at 10A/s, optimised ramp (7) reduces it by a factor ~ 16

Requirements: ⁶

Pilot	$N_p \approx 5e9$	$\pm 1-2$ mm	± 0.1	± 10	-
Stage I (43x43)	$N_p > 5e10$	$\pm 1.8 \sigma / 1 \sigma$	± 0.015	$\pm 1-10$??	$\pm 1e-4$

- 1: J. Wenninger: "Observation of Radial Ring Deformation using Closed Orbits at LEP"
- 2: RST, "Analysis of Ground Motion at SPS and LEP, implications for the LHC", CERN-AB-XX (to be published)
- 3: M. Haverkamp, "Decay and Snapback in Superconducting Accelerator Magnets", CERN-THESIS-2003-030
L. Bottura, "Cold Test Results: Field Aspects", Proceedings of Chamonix XII
L. Bottura, "Superconducting Magnets on Day 1", Proceedings of Chamonix XI
FQWG-Homepage: <http://fqwg.web.cern.ch/fqwg/>
- 4: W. Venturini: "Hysteresis measurements of a twin aperture MCB orbit corrector", 19th October 2005
- 5: Q. King, L. Ceccone: private communications
- 6: T. Wijnands, "Requirements for Real Time Correction of Decay and Snapback [...]", EPAC'00, Vienna, 2000
- 7: L. Bottura, "LHC Main Dipoles Proposed Baseline Current Ramping", LHC Project Report 172




→ closed Orbit drifts after 10 hours $\approx 0.3 \sigma$

- **LHC cleaning System:** $< 0.3 \sigma$ IR3,IR7
- **Machine protection & Absorbers:**
 - TCDQ (prot. asynchronous beam dumps) $< 0.5 \sigma$ IR6
 - Injection collimators & absorbers $\sim 0.3 \sigma$ IR2,IR8
 - Tertiary collimators for collisions $\sim 0.2 \sigma$ IR1,IR5
 - absolute numbers are in the range: $\sim 100\text{-}200 \mu\text{m}$
- **Inj. arc aperture w.r.t. prot. devices and coll.:** $< 0.3\text{-}0.5 \sigma$ (??) global
 (estimated arc aperture 7.5σ vs. Sec. Coll. @ 6.7σ)
- **Active systems :**
 - Transverse damper, Q-meter, PLL BPM $\sim 200 \mu\text{m}$ IR4
 - Interlock BPM $\sim 200 \mu\text{m}$ IR6
- **Performance :**
 - Collision points stability minimize drifts IR1,2,5,8
 - TOTEM/ATLAS Roman Pots $\sim 10 \mu\text{m}$ IR1,IR5
 - Reduce perturbations from feed-downs $\sim 0.5 \sigma$ global
 - Maintain beam on clean surface (e-cloud) $\sim 1 \sigma$?? global


... requirements are similar → distinction between local/global less obvious!

FB vs. FF: When is which applicable?

- Border is rather fuzzy.... injection likely won't require RT-feedbacks
- S. Sanfilippo (SM18 Review): “Decay of these magnets not scalable yet.”
 - b_3 & b_1 decay prediction:




random b_3 → negligible effect
 systematic b_3 → seem to be reproducible
 → constant feed-forward function may be established at some point of time



random b_1 → perturbs orbit
 systematic b_1 → $\Delta p/p$ shift
 → both require feedback control for each fill

Orbit Feedback Disturbance Rejection

- Low sensitivity to optics uncertainties = high disturbance rejection:
 - LHC simulation: Inj. Optics B1&B2 corrected



$\#\lambda_{\text{svd}}$ controls
correction precision

$$\text{attenuation} = 20 \cdot \log \left| \frac{\text{orbit r.m.s. after}}{\text{orbit r.m.s. before}} \right|_{\text{ref}}$$

- Robust Control: OFB can cope with up to about 100% β -beat!!** (we will do better!?!)
- Available aperture and collimation inefficiency w.r.t. β -beat is clearly more an issue
- Similar for BPM and COD calibration constants (hysteresis, see later talk)

- Induced noise on orbit¹:

- BPM failure (undetected electronics drift): $\Delta x|_{\max} < 0.01 (\beta_{\min}) / 0.4 \sigma (\beta_{\max})$
- BPM systematic (intensity, bunch length, 450 Gev): $\Delta x|_{\max} < 0.02 (\beta_{\min}) / 0.01 \sigma (\beta_{\max})$
- White BPM noise (single bunch): $\Delta x|_{\max} < 10^{-3} \sigma (\text{inj}) / 0.02 \sigma (\text{coll})$
- COD power converter ripple (~7mA/55A): $\Delta x|_{\max} < 0.1 \sigma$
- COD circuit failure (e.g. quench): $\Delta x|_{\max} \sim 0.8 \sigma$

→ compatible with nominal → should not pose problems for Stage I++

- Some comments:

- BPM resolution scales reciprocal with collimation requirement
 - Increased number of bunches
 - Tighter collimation tolerances
 - better BPM resolution Δx :

$$\Delta x = \frac{1}{\sqrt{N_{\text{turns}} \cdot N_{\text{bunch}}}} \sum_{N_{\text{turns}} \approx 224} \sum_{N_{\text{bunch}}} \Delta x_{\text{turn}}$$

(Nominal performance: beta-beat < 20 %, reasonable BPM calibration)

¹ R. Steinhagen, "Closed Orbit and Protection", MPWG #5x, 2005-12-16

Common Feedback/Feed-forward Control Layout

Technical implementation:

- Simple streaming task for all feed-forwards/feedbacks:
 - (Monitor \rightarrow Network)_{FB} \rightarrow Data processing \rightarrow Network \rightarrow PC-Gateways
- Feed-forward/Feedback choice mainly depends on available measurement
- Assumption on hardware present during startup of commissioning with beam:
 - General infrastructure (network, databases, controls software....)
 - Corrector circuits with rough (~20%) calibration and correct polarity
 - **Either: beam diagnostics or: good model for the to be steered parameter**
 - Timing on second level sufficient

