



LHC – A Glimpse on 2007




Ralph J. Steinhagen

**Accelerators & Beams Department, CERN
3rd Physics Institute, RWTH Aachen**



- LHC Status
 - Cryogenic system
 - Magnet procurement
 - Installation and hardware commissioning
- Revised beam commissioning plans in 2007
- Questions & Answers

Geneva, Switzerland – aerial view



Alps

Lac Lemman

Geneva

Airport

CERN

LHCb

ATLAS

ALICE

LHC


CMS

~8 km



LHC = Large Hadron Collider

- 27 km circumference, depth ~ 100 m
- accelerates two positively charged beams
 - two machines in the same tunnel
- eight-fold symmetry
 - four crossing insertions
- parameters for physics
 - p-p collisions at
 - $E_{\text{cms}} = 14 \text{ TeV}$ ($E_{\text{beam}} = 7 \text{ TeV}$)
 - nominal $L = 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$
 - Pb-Pb:
 - $E_{\text{cms}} = 1148 \text{ TeV}$
 - nominal $L = 10^{27} \text{ cm}^{-2} \text{ s}^{-1}$




protons @ 450 GeV
injection from the SPS


- 137th meeting of the CERN Council 2006-06-08:
 - [...] “experience indicates that [the proposed schedule] is the most efficient way to get to high energy, high luminosity operation at the earliest date.”
 - “Nevertheless, installation presents its own logistical hurdles that will need to be overcome on the way. “With a project such as the LHC, **there are bound to be challenges**,” said CERN Director General Robert Aymar, “however, the teams constructing the LHC and its detectors have risen to meet these challenges in the past, and I am convinced that **they will do so again**.”

- Short:
 - Commissioning with beam starts October/November 2007 followed by
 - Two months of “engineering”/calibration run with collisions at 450 GeV
 - Commissioning to full 7 TeV in 2008

LHC Cryogenic System




LHC Progress Dashboard: Cryogenic System



Legend		
Cryogenic Distribution Line	QSC_(A,B,C): Warm Compressor Station	Electrical Feed Box
Under commissioning	QSR_(A,B): Surface 4.5 K Refrigerator Cold Box	Superconducting Link
Delivered / Under installation	QURA: Underground 4.5 K Refrigerator Cold Box	Ordered (Contract placed)
Under fabrication	QURC: 1.8 K Refrigeration Unit Cold Box	Under definition
Under definition	QUI_(A,B,C): Cryogenic Interconnection Box	


Once, not a very unfamiliar view at CERN





But what was once common life at CERN ...






- The huge number of stored dipoles
 - **large logistics involved**: magnet assembly → storage → final tests → storage → installation in tunnel
 - ...allowed matching each individual slot to a specific dipole and opened the opportunity to minimise the effect of field quality differences between individual magnets
 - ... similar to “good wine”: magnet's mechanical, field quality and quench performance seemed to be preserved/improved (see Chamonix XIV: D. Tommasini)

(→maybe an indication for LHC?)




LHC Progress Dashboard: Cryodipoles






LHC Progress Dashboard: Short-Straight-Sections SSS



DPG Graduate's College, Bad Honnef, Ralph.Steinhagen@CERN.ch, 2006-08-31


LHC Underground: Magnet Interconnections



Magnet Interconnections: Learning Curve



Production rate 4-5

from P. Fessia



- Interconnect rate of one team in sector 4-5
 - Since mid-May: 2 teams in 7-8 (6 days/wk) and 1 team in 8-1 (4 days/wk)


...somewhere in USC 55



X marks the spot!


Installation and Commissioning Schedule - HOWTO

■ Cross-incompatibilities between certain tasks!





Revised Installation and Commissioning Schedule




Commissioning Schedule Detail

	56	67	78	81	12	23	34	45
Oct						Minimum HWC		
	Operations testing				Minimum HWC	Operations testing		
Nov	Full Machine Checkout (TI8 & TI2, Access, Vacuum, Equipment Tests, Cycle and Set, BIC and INB)							
	Beam Commissioning to 450GeV 16days estimated, 60%efficiency assumed							
Dec	Engineering run (Collisions at 450GeV + Ramp Commissioning)							

- An important milestone for both – LHC and its experiments!
 - Magnet alignment, polarities, rough calibration of magnets, injection optics
 - beam instrumentation, timing, control software
 - machine/experiment interfaces, ..
 - (detector alignment, triggers ...)




Calibration Run 2007 – “Phase 0”: Parameters



K_b	43	43	156	156
$I_b (10^{10})$	2	4	4	10
$\beta^* (m)$	11	11	11	11
Intensity per beam	$8.6 \cdot 10^{11}$	$1.7 \cdot 10^{12}$	$6.2 \cdot 10^{12}$	$1.6 \cdot 10^{13}$
Beam energy (MJ)	.06	.12	.45	1.1
Luminosity	$2 \cdot 10^{28}$	$7 \cdot 10^{28}$	$2.6 \cdot 10^{29}$	$1.6 \cdot 10^{30}$
Event rate ¹ (kHz)	0.7	2.8	10	65
W rate ² (per 24h)	0.8	3	11	70
Z rate ³ (per 24h)	0.08	0.3	1.1	7

1. Assuming 900 GeV inelastic cross section 40mb
2. Assuming 900 GeV cross section $W \rightarrow \mu\nu$ 0.5nb
3. Assuming 900 GeV cross section $Z \rightarrow \mu\mu$ 50pb

Staged Commissioning for Protons @7TeV in 2008/2009




- I. Pilot physics run at 7TeV
 - First collisions
 - 43 bunches, no crossing angle, no squeeze, moderate intensities
 - Push performance
 - Performance limit $10^{32} \text{ cm}^{-2} \text{ s}^{-1}$ (event pileup)
- II. 75ns operation
 - Establish multi-bunch operation, moderate intensities
 - Relaxed machine parameters
 - Push squeeze and crossing angle
 - Performance limit $10^{33} \text{ cm}^{-2} \text{ s}^{-1}$ (event pileup)
- III. 25ns operation I
 - Nominal crossing angle
 - Push squeeze
 - Increase intensity
 - Performance limit $2 \cdot 10^{33} \text{ cm}^{-2} \text{ s}^{-1}$
- IV. 25ns operation II (only after installation of full beam dump and collimators)
 - Push towards nominal performance


(10^6 seconds @ $\langle L \rangle$ of $10^{33} \text{ cm}^{-2} \text{ s}^{-1} \rightarrow 1 \text{ fb}^{-1}$) 29



Estimated Times for 2008



- We may benefit here from Engineering Run:
 - System tests, Polarities, Calibrations, ...
 - learning curves



DPG Graduate's College, Bad Honnef, Ralph.Steinhagen@CERN.ch, 2006-08-31




There's also the PS and SPS

- 2006: Successful restart of PS and SPS
 - minor hiccup: phase compensators
 - New SPS control system (test for future LHC)
- Commissioning of
 - CNGS beam line (CERN Neutrinos to Gran Sasso)
 - TT60 (LHC: Beam 1)



All accelerator operation now in CCC



Some Issues at the LHC related to Beam Stability

- All HEP particle quests reach a point where:

$$\dot{N}_{event} = L \cdot \sigma_{signal} \quad \text{with} \quad \frac{\sigma_{signal}}{\sigma_{background}} \ll 1 \quad @ \text{ achievable Energy } E$$

- Push achievable energy E:
 - Minimise synchrotron radiation losses:
 - $e^+e^- \rightarrow$ hadrons collider (p^+p^\pm, \dots)
 - Choice: linear vs. circular
 - Optimise RF cavities + normal conducting magnets (CLIC, ILC)
 - Standard RF cavities + superconducting magnets (TeV, RHIC, LHC)
 - LHC: superconducting NbTi alloy @ 1.9K
 - temperature increase due to e.g. particles losses are an issue
- Push maximum peak luminosity
 - essentially: increase number of particles inside the machine

Storage ring design:

$$L = \frac{N^2 k f_{\text{rev}}}{4 \pi \sigma_x \sigma_y} \cdot e^{-\frac{1}{4} \left[\left(\frac{\Delta x}{\sigma_x} \right)^2 + \left(\frac{\Delta y}{\sigma_y} \right)^2 \right]} \cdot F_{\text{crossing}} \cdot F_{\text{hour glass}} \dots$$

- N : number of particles per bunch,
- k : total number of bunches,
- σ_x, σ_y : hor./vert. r.m.s. beam size in IR
- f_{rev} : revolution frequency,
- Δ_x, Δ_y : hor./vert. beam separation in IR
- $F_{\text{crossing}}, F_{\text{hourglass}}$: numerical form factors,


	LHC	Tevatron
	$N_{\text{pilot}} = 5 \cdot 10^9, N_{\text{nominal}} = 12 \cdot 10^{10}$	$N_p = 30 \cdot 10^{10}$
	$k = 1 \dots 2808$	$k = 36$
	$\sigma_x = \sigma_y \sim 17 \mu\text{m}$	$\sigma_x = \sigma_y \sim 30 \mu\text{m}$
	$f_{\text{rev}} = 11.2 \text{ kHz (fixed)}$	$f_{\text{rev}} = 47.7 \text{ kHz}$
	$F_{\text{cross.}} (285 \mu\text{rad}) \sim 0.8$	$F_{\text{cross.}} (0) = 1$
	$1 - F_{\text{hourgl.}} \sim 0.4\%$	$1 - F_{\text{hourgl.}} \sim 38\%$

Most parameters are defined by the accelerator geometry and lattice

The “most effective” parameter: total stored intensity $I_{\text{stored}} = Nk$

LHC: $I_{\text{stored}} \approx 3.2 \cdot 10^{14} \text{ protons} \Rightarrow E_{\text{stored}} \approx 350 \text{ MJ @ } 7 \text{ TeV}$

IWBS'04: "LHC is a pretty dangerous machine" Livingston Style plot



Maximum LHC Energy of 7 TeV

- LHC superconducting dipoles may loose superconducting state (“quench”)
 - minimum quench energy E_{MQE} @7 TeV for $t \sim 10 - 20$ ms

$$E_{MQE} < 30 \text{ mJ/cm}^{-3} \text{ vs. } E_{stored} = 350 \text{ MJ/beam (nominal LHC)}$$

$$\text{(or: } N_{loss} < 10^8 \text{ protons/m vs. } N_{total} \sim 3 \cdot 10^{14} \text{ protons)}$$

→ sufficient to quench all magnets and/or may cause serious damage


- requires excellent control of particle losses

- Example: un-controlled vs. controlled energy release



C = $5.4 \cdot 10^{12}$ protons @ 450 GeV
 D = $7.9 \cdot 10^{12}$ protons @ 450 GeV

Vacuum pipe of QTRF in TT40




for details see: Chamonix XIV:
 “Damage levels - Comparison of Experiment and simulation” and PAC'05

courtesy V. Kain

What happens if a particle is unstable and lost? → Collimation and Protection System

Two-stage cleaning system:





experiments

– requires tight orbit stability requirement of $\sigma/6$:

$\sim 25 \mu\text{m}$ at coll. jaws & 7 TeV → less than the thickness of a human hair

experiments



- “LHC is on the horizon”
 - CERN Council confirmed schedule for commissioning with beam in 2007:
 - Commissioning with beam starts October/November 2007 followed by
 - Two months of “engineering”/calibration run with collisions at 450 GeV
 - Commissioning to full 7 TeV in 2008

- LHC operation is very challenging
 - Unprecedented high stored energy per beam in a superconducting environment that does not tolerate particle losses
 - Maximum possible LHC performance may be limited by the stability of the beam and the ability to control particle losses inside the machine.
 - LHC is the first machine that relies on orbit feedbacks for a safe and reliable machine operation.