

An accelerator perspective on:

LHC Interaction Point Stability

or


“How well do we know the beam line”

Ralph J. Steinhausen

Degradation of Nominal Luminosity


$$L = L_0 \cdot e^{-\frac{1}{4} \left[\left(\frac{\Delta x}{\sigma_x} \right)^2 + \left(\frac{\Delta y}{\sigma_y} \right)^2 \right]} \cdot F_{crossing} \cdot F_{hour\ glass} \cdot \dots$$

- Effective beam overlap:




- geometric optics: beam overlap at IP \leftrightarrow beam position stability at BPMSW
 - nominal: $\sigma^* \approx 15 \mu\text{m}$, e.g. 1σ overlap at IP $\rightarrow 15 \mu\text{m}$ stability at BPMSW
- N.B. nom. crossing angle “guarantees” one plane overlap (long. shift $\ll 20 \mu\text{m}$)

- Beam stability analysis depends on the choice of reference system:
 - beam position measurements (different for B1 & B2!)
 - magnetic quadrupole centre (minimising feed-down effects)
 - geometric quadrupole centre (maintaining aperture constraints)
 - external reference
- Some definitions:




- Beam Position Measurement:
 - electrical BPM bias: 100 µm r.m.s.
 - electrical BPM centre w.r.t. geometric quad. centre: 200 µm r.m.s.
 - after aperture scan: < 50-100 µm r.m.s.
 - electrical BPM centre w.r.t. geometric quad. centre: 200 µm r.m.s.
 - after k-modulation: < 50 (5?) µm
- Survey group targets for magnet alignment:
 - 0.2 mm r.m.s. globally
 - 0.1 mm r.m.s. as an average over 10 neighbouring magnets
 - N.B. Orbit FB: working assumption: 0.5 mm r.m.s.
 - Watch out: CLIC-Note-422, CERN-THESSIS-2001-010
→ final focus stability might be determined by systematic drifts

Micron Stability of the Triplet Installation in the Presence of Ground Motion and Thermal Drifts



Ventilation du tunnel LEP/LHC



- Mechanism: Orbit feedback intrinsically aligns with respect to the BPMs that are either attached to the quadrupoles or have similar girders
- Thermal expansion, steel $\alpha_{\text{steel}} \approx 10-17 \cdot 10^{-6} \text{ K}^{-1}$ (BS:970, DIN18800):

$$\Delta x = x_0 \cdot \alpha \cdot \Delta T$$

- Systematic shift of beam reference system with respect to non-moving external reference (e.g. potentially collimators):
 - Cryo-Magnets: $x_0 \geq (340 \pm 20) \text{ mm}$ $\rightarrow \Delta x \approx 3.4 - 5.8 \mu\text{m}/^\circ\text{C}$
 - Warm equipment: $x_0 \approx 950 \text{ mm}$ $\rightarrow \Delta x \approx 9.5 - 16 \mu\text{m}/^\circ\text{C}$
- The inlet temperature is stabilised to about $\pm 1^\circ\text{C}$
 - **temperature changes shouldn't pose a problem for even IRs**

- Left-Right temperature gradient:

tunnel air:


$$T_1 \approx 23 \pm 6 \text{ }^{\circ}\text{C}$$

cavern:

$$T_3 \approx 23 \pm 6 \text{ }^{\circ}\text{C} (?)$$


tunnel right:

$$T_2 \approx 23 \pm 6 \text{ }^{\circ}\text{C}$$



- $T_1 \neq T_2 \neq T_3$
 - powering of arc equipment (CODs, ...) → dyn. heat-load asymmetry
 - IR4 (RF, BI) → IP5 ← IR6 (beam extraction)
- Working assumption: $\Delta T = |T_2 - T_1| \approx \pm 1 \dots 2 \text{ }^{\circ}\text{C}$ → $\Delta x_{\text{thermal}} \approx 16 \dots 32 \mu\text{m}$

- However, temperature variations in odd IRs might be larger due to different thermal loads in neighbouring arcs.
- Special case: Collimation in IR7




- Closed air circulation in IR7: T estimate as high as 35°C
- Already $\Delta T = \pm 2^\circ\text{C} \rightarrow \Delta x \approx \pm 20 \mu\text{m}$, Collimation: $\pm 50 \mu\text{m}$ might be tolerable (TOTEM 10 μm requirements – a midnight summer dream?)
- CNGS/Ti8: Estimates where $\approx 10^\circ\text{C}$ off (measured 25°C vs. estimated 35°C)
- Wait for LHC commissioning with beam and real temperature experience

- *Mike: "How well do you (we) know the beamline at the interaction point?"*
 - without beam-based alignment: $\Delta x \approx 300\text{-}600 \mu\text{m r.m.s.}$
 - for details: LHC Collimation WG Meeting #79
 - with beam-based alignment: $\Delta x \approx 5 \mu\text{m r.m.s.}$
 - after k-modulation, Lumi-scans (my “guess”)
- *Mike: "Will it change within a run or to the next run/fill?" - Yes*
 - stability without orbit feedback but “perfect” feed-forward of last cycle
 $\Delta x \approx 300 - 600 \mu\text{m r.m.s.}$
 - for details: LHC Collimation WG Meeting #79
 - stability with orbit feedback:
 - w.r.t. geometric cold quad. centre: $\Delta x \approx 5\text{-}7 \mu\text{m r.m.s.}$
 - assumes nominal FB operation
 - w.r.t. geometric warm quad. centre: $\Delta x \approx 20\text{-}30 \mu\text{m r.m.s.}$
 - limited by thermal gradients
 - w.r.t. ext. reference (e.g. CMS detector): $\Delta x \approx 30\text{-}50 \mu\text{m r.m.s.}$
 - limited by ground motion and thermal drifts
 - Numbers assume perfect fill-to-fill beam parameters reproducibility
 - does not include long-term BPM stability: → I will verify this issue!





Reserve Slides




LHC Orbit Feedback Test at the SPS II/II


- Stabilisation “record” in the SPS
 - 270 GeV coasting (proton) beam,
72 nom bunches, $\beta_v \approx 100$ m
 - rivals modern light sources
 - magnitudes better than required
- Target: maintain same longterm stability
 - thermal drifts, dependence on beam parameter, ...



- 43x43 operation: max. intensity $4 \cdot 10^{10}$ protons/bunch
- No gain-switching: BPMs will always operate at 'high' sensitivity



- Special parallel to point focusing machine optic ($\beta_0 \approx 1600$ m)



- Roman Pots move close to the beam halo ($\sim 10\sigma$) and measure dN/dt down to:

$$t_{min} = (p \theta_{min})^2 \sim \frac{p^2}{\beta_0 \beta_d} \cdot x_{min}^2$$

- Requires good knowledge on
 - Beta-functions β_0 at IP and β_d at detector
 - Beam momentum p
 - minimum distance of roman pot x_{min} w.r.t. beam centre
- Desired: $\Delta L/L \approx 1\% \rightarrow \Delta t/t \approx 1\% \rightarrow \Delta\theta/\theta \approx \Delta x/x \approx 5 \cdot 10^{-3}$
 - absolute beam position stability at roman pot ($x_{min} \sim 1\text{mm}$) < 5 μm !!**
 - Understanding of systematics and alignment play an important role