



LHC Tune and Chromaticity Diagnostic and Feedback Control Systems

Ralph J. Steinhausen, AB-BI

for the 'invincible Gauls'

**A. Boccardi, F. Follin, M. Gasior, R. Jones, P. Karlsson,
G. Sivatskiy, R.J. Steinhausen, J. Wenninger**

- Base-line LHC Q, Q' and C⁻ diagnostics overview
 - System overview and hardware status

- Application overview

- Commissioning of Q, Q' and C⁻ beam parameter control
 - Instrumentation, diagnostics and related corrector circuits
 - Feedback options and setup


Reminder: LHC Tune and Chromaticity Requirements

- The measurement and control of
 - orbit, **tune, chromaticity**, energy and **coupling** --
 will be an integral part of the LHC operation

- Stability requirements summary (Chamonix'06):

	Orbit [σ]	Tune [$0.5 \cdot f_{rev}$]	Chroma. [units]	Energy [$\Delta p/p$]	Coupling [c ₋]
Exp. Perturbations:	~ 1-2 (30 mm)	0.025 (0.06)	~ 70 (140)	$\pm 1.5e-4$	~0.01 (0.1)
Pilot bunch	-	± 0.1	+ 10 ??	-	-
Stage I Requirements	$\pm \sim 1$	$\pm 0.015 \rightarrow 0.003$	> 0 \pm 10	$\pm 1e-4$	$\ll 0.03$
Nominal	$\pm 0.3 / 0.5$	$\pm 0.003 / \pm 0.001$	1-2 \pm 1	$\pm 1e-4$	$\ll 0.01$


- ... “FBs are most beneficial and (likely) required before the very first ramp!”
- after two years, experience from RHIC/Tevatron and many MDs in the SPS
 - ... we are ready and believe to be prepared to meet the LHC challenge!



- Exp. perturbations are about 200 times than required stability!
- however: maximum drift rates are expected to be slow in the LHC
 - Tune: $\Delta Q/\Delta t|_{\max} < 10^{-3} \text{ s}^{-1}$
 - Chromaticity: $\Delta Q'/\Delta t|_{\max} < 2 \text{ s}^{-1}$ ← the critical/difficult parameter
- Requires active control relying on beam-based measurements


LHC Q Base-Line Q Instrumentation

Back-bone: Base-Band-Q Principle on a Slide



- **Basic principle: AC-coupled peak detector**
 - no saturation, self-triggered, no gain changes between pilot and nominal
 - intrinsically down samples spectra: ... 6 GHz \rightarrow 1kHz ... f_{rev}
 - Base-band operation: very high sensitivity/resolution ADC available
 - Measured resolution estimate: < 10 nm \rightarrow ϵ blow-up is a non-issue
- One of the few turn-key systems in the LHC
 - **easy/very fast commissioning** – done in parallel with RF capture

- Back-bone: Base-Band-Q Meter¹ (BBQ)
 - well tested and proven solution: SPS, LEIR, PSB, RHIC, Tevatron, ...
- Pick-ups: 40 cm strip-lines
- Shakers: 1 m strip-lines
 - magnetic deflectors driven ± 3 A max.
 - working bandwidth: 1 - 6 kHz
 - maximum kick angle: $0.1 \text{ nrad}@7\text{TeV}$
 → $23 \text{ nm}@\beta = 180\text{m}$ per turn
- 3 x 2 (nearly) identical installation (tunnel (2 development/hot-spare systems on the surface))
- ... some redundancy:
 8 systems available vs. 2 needed



¹M. Gasior: LHC-Project-Report-853


- BBQ based systems: (~ 1 more week)
 - all acquisition systems are in place
 - remaining: front-end installation, final cabling and HW acceptance test
 - N.B. transverse damper available as exciter
- Head-Tail/Fast-Intra-Bunch-Position Monitor
 - acquisition system (scopes) in place
 - final cabling pending (~ 2 days, April)
- Schottky: US-LARP responsibility (soonish)
 - cabling, detectors in place
 - HW, SW acquisition and control system pending
- we are in good shape and ready for first beams... whenever we get the 'go-ahead'

UA47-BY12 & BY13

Head-Tail

BBQ-FFT1/2
'on-demand'

Schottky




2008-01-16

Commissioning Phase A.3 (choices first circulating beam):

- **FFT based acquisition using LHC BPMs - Phase A.2** → J. Wenninger, V. Kain (excite and/or analyse injection oscillation spectra)
 - initial tune adjustments (first 100 turns, integer Q, local C⁻ correction, etc.)
 - CON: slow, **no fast periodic acquisition possible, problematic with large Q'**
- **FFT based acquisition using LHC BBQ** with either
 - simply **no excitation!** - yields sufficient data in most cases...
...for the others: fall-back to one of the following excitation based methods:
 - **'RF transverse damper'** or 'BQK' (aka. 'tune shaker'),
 - preferred choice: no timing required, fast and easy amplitude tuning
 - **'MKQA'** (aka. 'tune' or 'aperture kicker') triggered by the MTG
 - mainly for cross-calibration and measurements involving BPMs or HT
 - CON: slower tune (→ chromaticity) tracking, **problematic with large Q'**
- **Phase-Locked-Loop (PLL) based acquisition**
 - requires excitation using either the **'BQK'** or 'RF transverse damper'
 - can cope with wide range of Q', SPS experience: robust measurement

- Three independent BBQ Tune/Coupling diagnostic chains available per beam:
 - PPL based acquisition of Q, Q'...
 - one measurement at high/reduced acquisition frequency, targets:
 - 100 Hz for feedbacks (driven by need to reduce feedback latencies)
 - 1 Hz for general purpose logging
 - expert: high frequency data that is event synchronised and buffered (post-mortem, PLL setup), typical length: 5 min \leftrightarrow < 1 MB of data
 - main use: monitoring/logging, feedbacks, fill-to-fill studies, ...
 - FFT based acquisition of Q,Q'... – 'periodic'
 - one measurement every 1 second starting from first-injection
 - intended use: monitoring/logging, (feedbacks), fill-to-fill studies, ...
 - FFT based acquisition of Q,Q'... – 'on demand'
 - n-measurements synchronised to an external event (BPM, BQ, ...)
 - intended use: expert diagnostics, detailed studies, ...



- Tested and/or used at SPS, PSB, PS, LEIR for about a year now (~debugged)
- Main responsibility: R. Steinhausen (AB-BI), co-maintained and input from F. Follin, J. Wenninger (AB-OP)

- Same interface/can acquire from any CERN BBQ-FFT/PLL based system
 - same diagnostics look-and-feel across accelerators
 - several different FFT analysis tools available
 - Standard displays: Q/Q' traces, FFT-vs-time, FFT spectra, S/N ratios, raw oscillation data, BTF, ... → modular, can be used as a fixed-display
 - standard CO interfaces: SDDS, LSA, JAPC, timing where applicable
 - developed having commissioning and expert diagnostics in mind
 - however: provides reduced level of detail for day-to-day operation
 - off-line diagnostics, re-tuning, comparison and expert analysis of multiple Q/Q' parameters and data sets possible
- additional LHC specific 'plugins':
 - Q/Q' 'slow' steering ('one point trim'), kick/BPM timing synchronisation,
 - Q/Q' real-time feedback control:
 - implements the same algorithms as the Q/Q' feedback controller
 - any tested settings are easily applied to the Q/C-Q' FB controller
- Some features in the testing/development pipeline...



LHC Base-Line Q/Q' Diagnostics Overview – Q/C- TuneViewer – Functional Overview II/II



LHC Tune and Chromaticity Diag. & FB Control Systems, Ralph.Steinhausen@CERN.ch, 2008-03-06

File Configure
Help

N-Turn FFT Phase-Locked-Loop
Contour Mag H H ACQ# 13

Acquisition Settings

Machine cycle: + SFTPRO1

Acquisition Length [turns]: 1024

Measurement Rate (Period): 40 Hz (25 ms)

Start [ms]: 20

Stop [ms]: 4,220

Type of Excitation: OFF

get set

Excitation
Tune Fitter
Misc

Excitation Settings

Hor. [%]:
0
100
50

Ver. [%]:
0
100
10

horizontal: min: 0.3 max: 0.42


vertical: min: 0.35 max: 0.47

Comments: no comment Detach Viewer

▶
▶
▶▶
||
■


Trace Mag H H ACQ# 13
Trace Mag V V ACQ# 13

horizontal tune [frev]





time [s]

vertical tune [frev]




time [s]



LHC Base-Line Q/Q' Diagnostics Overview – Q/C- Betatron-Coupling Measurement

- No orbit, Q, Q' feedback without control of betatron-coupling
- FFT/PLL measures eigenmodes that in the presence of coupling are rotated w.r.t. “true” horizontal/vertical tune
 - $A_{1,x}$: “horizontal” eigenmode in vertical plane
 - $A_{1,y}$: “horizontal” eigenmode in horizontal plane



$$r_1 = \frac{A_{1,y}}{A_{1,x}} \quad \wedge \quad r_2 = \frac{A_{2,x}}{A_{2,y}}$$

$$\Rightarrow \boxed{|C^-| = |Q_1 - Q_2| \cdot \frac{2\sqrt{r_1 r_2}}{(1 + r_1 r_2)} \quad \wedge \quad \Delta = |Q_1 - Q_2| \cdot \frac{(1 - r_1 r_2)}{(1 + r_1 r_2)}}$$


- Decoupled feedback control:
 - q_x, q_y → quadrupole circuits strength
 - $|C^-|, \chi$ → skew-quadrupole circuits strength


first implemented and tested at RHIC/
tested/operational at CERN




LHC Base-Line Q/Q' Diagnostics Overview – Q/C- Betatron-Coupling Measurement (Real-Beam Data)

LHC Tune and Chromaticity Diag. & FB Control Systems, Ralph.Steinhausen@CERN.ch, 2008-03-06







- either: $\Delta Q/\Delta t|_{\text{max}} \approx 0.3$ within 300 ms, (o. of magnitude faster than LHC requirement)
- or: **tune resolution: $\Delta Q_{\text{res}} \approx 10^{-6} \dots 10^{-7}$ but reduced bandwidth ($\sim 1..2 \text{ Hz}$)**

- RF momentum modulation – LHC Commissioning Phase A.3
 - class: Q' is proportional to momentum induced tune changes

$$Q' = \frac{\Delta Q}{\Delta p / p}$$


← *the measured tune change*
← *the RF induced momentum change (known)*

- Kicked Head-Tail Phase-Shift – LHC Phase A.3 (~ copy++ of SPS installation)
 - multiple dependences on beam parameter other than Q'
 - limited by emittance growth/orbit budget → it's an MD tool
 - still provides good cross-reference and general beam diagnostics!
- Side-exciter/BTF based method – end 2008/beginning of 2009
 - needs broader acceptance (human component) and assessment with LHC beam (parameters)
- Continuous Head-Tail Phase-Shift – 2009++
 - Tested various schemes in 2007 at the SPS but need further assessment

Q' through RF momentum modulation based method

- There are multiple but similar detection techniques:
 - modulation below Q_s → classic schoolbook example
 - modulation above Q_s → Brüning's and/or McGinnis' method

$$Q' = \frac{\Delta Q}{\Delta p/p}$$



- LHC RF power permits only slow modulation (J. Tückmantel et al.)

Q' through RF momentum modulation based method

- Controllability of Q' depends on ability to track the tune both accurately & fast

- intrinsic to this problem: $\Delta Q_{res}^{(\cdot)} \cdot \Delta t_{res} = const.$

- LHC expectations:

- Tune: $\Delta Q/\Delta t|_{max} < 10^{-3} \text{ s}^{-1}$
 - Chromaticity: $\Delta Q'/\Delta t|_{max} < 2 \text{ s}^{-1}$
- } “slow” compared to Q/Q' drifts
e.g. in the SPS/RHIC/CPS/PSB

→ Chose to tackle the LHC Q' measurement in the high accuracy limit:

- very small but slow $\Delta p/p$ modulation while tracking Q with a PLL

- f_{mod} : 0.5 Hz (setup) → 5 Hz (nominal)
- $\Delta p/p$: $\sim 10^{-4}$ (setup) → $\sim 10^{-5}$ (nominal)

- Feasibility supported by LHC Q' tracker prototype tests in the SPS

- $f_{mod} = 0.5 \text{ Hz}$, $\Delta p/p = 2 \cdot 10^{-5}$: $\Delta Q_{res} \sim 10^{-5}$, $\Delta Q'_{res} < 1$
- limited by the f_{mod} DAC quantization






FFT Based Q Acquisition


$\Delta p/p \sim 2 \cdot 10^{-5}$ driven Q modulation ($Q'_v \sim 36$ units)




LHC Tune and Chromaticity Diag. & FB Control Systems, Ralph.Steinhausen@CERN.ch, 2008-03-06







- real-time Q' detection algorithm (agrees with SPS cross-calibration):
 - Q' resolution better than 1 unit (nominal performance) → reproducible
- N.B. tracking transients: $\Delta Q'$ feed-down on ΔQ (non-centred orbit)
 - $\Delta Q/\Delta t \gg \Delta Q'/\Delta t \rightarrow$ SPS specific, LHC: $\Delta Q/\Delta t|_{\max} < 10^{-4}/s$



- Scans to assess the maximum useful range yield showed that this method can cope with values of Q' up to at least 34 units
 - larger than (any other) Fourier based method ... (usually damping limited)


LHC Base-Line Q/Q' Diagnostics Overview – Q' Q' Through Kicked Head-Tail Phase Shift

- First order: copy of SPS system

- increased sampling: 5000 (LHC) vs. 2000 (SPS)
- increased bandwidth: > 3 GHz vs. 2 GHz
- **switch on & use system**

- Some intrinsic limitations:

- requires large kicks; issues:
 - sig. emittance blow-up
 - machine protection → **measurement remains a MD/pilot beam tool!**




- uncertainties due to multiple dependences on beam parameter other than Q':

- Impedance, **non-linear damping** (Q'/Q'', RF damper), non-lin. Q_s ,
- Very low LHC $Q_s = 30$ Hz issue
→ **oscillations need to prevail > 350++ turns for useful Q' analysis**



- BI-expert tool known and used by many in ABP, BI, OP & RF
- Misnomer: 'Head-Tail' is actually a 'Fast-Intra-Bunch-Position-Monitor'
 - many long. and trans. beam diagnostics cross-calibrations possible
 - Implements standard analysis/displays for:
 - Raw and phase compensated Sum/Difference signal oscillation data
 - Tune, betatron-coupling, closed orbit, bunch length-vs-time
 - Phase-evolution-vs-turn → Q'-vs-turn, HT-Q' estimate
 - Amplitude-envelope (damping/instability growth times),
 - 1D-trace & 2D longitudinal and transverse bunch spectra
 - in-bunch & coupled bunch mode instabilities, chromatic frequencies
 - ...
 - in the pipeline: fast relative bunch intensity changes, BPM type acquisitions, processing speed performance
 - off-line diagnostics, re-tuning, comparison and expert analysis of multiple longitudinal, Q, Q' data sets possible
- If you have questions, feel that something is missing or is too much (= bugs)
→ please let me know



Commissioning of the

Q, C- & Q'


Feedback Loops



Total Number of (FB) Corrector Circuits Powering Layout of the SSS Correction Scheme IP4↔IP5

LHC Tune and Chromaticity Diag. & FB Control Systems, Ralph.Steinhaugen@CERN.ch, 2008-03-06

Auxiliary bus-bars and connections for Short straight section correction scheme



Summary: Total Number of (FB) Corrector Circuits

- Orbit: 530 correction dipole magnets/plane (71% are of type MCBH/V, $\pm 60\text{A}$)
 - total 1060 individually powered magnets (60-120 A)
 - ~30 shared between B1 & B2
- Tune:
 - 16x $\pm 600\text{A}$ circuits powered from even IPs (2, 4, 6, 8), 2 families
 - independent for Beam 1&2, but coupling between planes
 - can use them independently, optional use of DS quadrupoles
- Chromaticity:
 - 32x $\pm 600\text{A}$ circuits powered from even IPs, 4 families ($\Delta Q' \sim 1 \rightarrow 1\text{A} @ 7\text{TeV}$)
- Coupling: four skew quadrupoles per arc, 1/2 families
 - Beam 1: 12x $\pm 600\text{A}$
 - Beam 2: 10x $\pm 600\text{A}$
- Total: 1130 of 1720 circuits/power converter → more than half the LHC is controlled by beam based feedback systems!

■ Divide:

- FB zoo: Orbit, Tune, Chromaticity, β -Coupling, Energy, ..., Luminosity, (Beta-Beating)
 - develop/commission on a one-by-one basis
- Feedback controller into:
 - Space Domain: $\Delta Q_{x/y}$ \rightarrow quadrupole circuits currents, etc.



- classic parameter control – pre-requisite for any beam steering

- Time Domain: compensate for dynamic behaviour

- relaxed controller for commissioning (low-bandwidth PI controller)

■ Conquer:

- Once feedback operation on a per-parameter basis is established, reintegrate and test/commission inter-loop coupling and other constraints.


■ LHC Feedback hierarchy:

- Orbit (Energy) \rightarrow Tune/Coupling PLL \rightarrow Q' Tracker \rightarrow Q/C-/Q' feedback

Future Integration of Q/Q' Measurements for Q/Q' Control

Full LHC Beam-Based Control Scheme

LHC Tune and Chromaticity Diag. & FB Control Systems, Ralph.Steinhausen@CERN.ch, 2008-03-06




further: $f_{BW}(PLL) \gg f_{BW}(Q') \geq f_{BW}(Q, C)$

LHC FBs: 2158 input devices, 1136 output devices → total: ~3300 devices!


Common Feedback/Feed-Forward Control Layout

Each LHC feedback controller implementation split into two sub-systems:

- **Service Unit:** Interface to users/software control system
- **Feedback Controller:** actual parameter/feedback control logic
 - Simple streaming task for all feed-forwards/feedbacks:
(Monitor \rightarrow Network) $_{FB}$ \rightarrow Data-processing \rightarrow Network \rightarrow PC-Gateways
 - Can run auto-triggered (**first beams**)
 - Hardware and functional specifications already available




- **Test-bed** complementary to Feedback Controllers:
 - Simulates the open loop and orbit response of COD→BEAM→BPM
 - Decay/Snap-back, ramp, squeeze, ground motion simulations, ...
 - Keeps/can test real-time constraints up to 1 kHz
 - Same data delivery mechanism and timing as the front-ends
 - transparent for the FB controller



- Most feedbacks checks can be and are done during hardware commissioning:
 - Interfaces and communication from BI and to PO front-ends (**done**)
 - Interfaces to databases, tune kicker, PLL FESA integration (**soon**)
- Using the 'test-bed' we will do the further tests without beam: (**in progress**)
 - analysis routines, time-domain and circuit failure interception routines
- Things that have to and can only be checked with beam:
 - PO-Circuits/BI-Instrument polarities, planes, mapping
 - reduced number of corrector circuits → ~ **1-2 shifts/FB**
 - PLL: beam transfer function and **rough test** of calibrations


} **is done while threading the first beam!**
- It is possible to run feedbacks already after above procedures:
 - auto-triggered at 0.1 – 1 Hz & lower closed loop bandwidth – “**day 1..N**”
 - In case of Q, Q' we will have the following options:
 - a) Input: 'FFT + peak detector' or PLL
 - b) Control level: TuneViewer GUI (slow) or Tune Feedback Controller (fast)
 - **both implement the same algorithms!**

- Essentially BTF and compensation consists of the adjustment of four parameters, preferably during injection plateau (stable tune and chromaticity)
 - 1st step: verify necessary excitation amplitude and plane mapping
 - 2nd step: verify long sample delay (once per installation, constant)
 - full range BTF (will be partially done also without beam)





- count $\pm\pi$ wrap-around \rightarrow number of delayed samples

■ Measure $d\phi/df$ slope (~ front-end non-lin. phase and kicker cable length)



■ Adjustments of the locking phase (tune-peak – phase matching)





- Based on commissioning experience at the SPS and RHIC:
 - provided stable circulating beam and absence of “surprises”, the initial PLL setup with beam can be quite fast: **< 30 minutes net!**
 - verification of proper loop operation in less than a minute (= one BTF)
- Including verification of circuit mapping and polarities:
 - **~2-4 half-shifts with per beam per feedback loop**

- Baseline Q/Q' diagnostics and controls is in good shape
 - compatible with large values of chromaticity and nominal LHC operation
 - Feedback architecture, strategies and algorithms are well established
 - same feedback architecture for orbit, tune/coupling, chromaticity...
 - LHC priorities: Orbit/Energy FB → Q/C PLL → Q' Tracker → Q/Q'/C- FB
- Commissioning of feedbacks:
 - Most of the requirements for a minimum workable feedback systems are already fulfilled after threading and establishing circulating beam
 - about two to four half shifts/beam/feed-back for PLL/FB specific procedures
 - Feedbacks are most useful when used at an early stage
 - feedback signals provide feed-forward information for next cycles
- 'Egg of Columbus' principle: LHC is not the first machine with a BBQ, Q/Q' PLL system or beam-based feedback system, however: there is no guarantee for 'no surprises' or perfect commissioning prior to real LHC operation!
 - We are well prepared but some things need to be tested with real beam!

... after the Q/Q' commissioning

Thank you for your attention
the Q(")auls






additional supporting slides

PLL based Q/Q' tracking study at the SPS

PLL Side Exciter (SEX) based Tune Width/Q' Measurement




- Resonant phase change \leftrightarrow tune width change
 - “free” real-time tune footprint measurement
 - measurable dependence of $\Delta Q \sim Q'$

driven 2nd order resonance:

$$\tan(\varphi) \approx \frac{\Delta Q \cdot \omega_Q \omega_D}{\omega_Q^2 - \omega_D^2}$$

PLL based Q/Q' tracking study at the SPS

PLL Side Exciter (SEX) based Tune Width/Q' Measurement




- Side-exciter phase ~~appears to~~ changes linearly with Q' (2007 MDs)
 - No additional momentum modulation
 - Absolute scale requires calibration w.r.t. to classic Q' measurement
 - Non-linear effects require further assessment → 2007 MD Target #2/3

- The feedback controller consists of three stages:

- 1 Compute steady-state corrector settings $\vec{\delta}_{ss} = (\delta_1, \dots, \delta_n)$ based on measured parameter shift $\Delta x = (x_1, \dots, x_n)$ that will move the beam to its reference position for $t \rightarrow \infty$.
- 2 Compute a $\vec{\delta}(t)$ that will enhance the transition $\vec{\delta}(t=0) \rightarrow \vec{\delta}_{ss}$
- 3 Feed-forward: anticipate and add deflections $\vec{\delta}_{ff}$ to compensate changes of well known sources

space domain

time domain



Reminder: Solution in Time-Domain


- LHC PC (LR circuit) model $G(s)$: rate-limited first order system with delays:

$$G(s) = \frac{e^{-\lambda s}}{\tau s + 1} G_{NL}(s)$$

τ : being the circuit time constant

$$D(s) = K_0 \cdot \left(\frac{\tau}{\alpha} + \frac{1}{\alpha} \right) \quad K_0: \text{l-to-}\delta \text{ transfer func.}$$



- Linear optimal PI controller:
- including non-linearities (delay & rate-limit):




$D_{PID}(s)$ gains are independent on non-linearities and delays!!

Some Results: Smith-Predictor and Anti-Windup

LHC Tune and Chromaticity Diag. & FB Control Systems, Ralph.Steinhausen@CERN.ch, 2008-03-06




with full delay and windup compensator scheme:




Nominal Feedback Response T_0

- Full LHC orbit simulation @1KHz sampling, (BPM sampling: 25Hz)





Nominal Feedback Disturbance Rejection S_{d0}

- Full LHC orbit simulation @1KHz sampling, (BPM sampling: 25Hz)



- Multiple FBs and measurements acting on the same RF cavity frequency (N.B. radial position limited by collimator gap)
 - Q' tracker, energy FB (\approx 'radial loop'), Q'' and other optics measurements
 - strategy: orbit feedback acts as a slave system controlling the RF
 - dispersion orbit is subtracted/not corrected by 'regular OFB'
 - energy FB corrects w.r.t. to the by the Q' tracker set reference


$$- \Delta f_{RF} = (\Delta f_{Q'} - \Delta f_{meas})$$




Reminder: Solution in Space-Domain

Response Matrix and Calibration Uncertainties

- Matrices are direct observables and can thus be measured with beam!
 - Imperfect optics and calibration errors may deteriorate convergence speed but not the convergence accuracy
 - Example: 2-dim error surface projection




BPM Reading (μm)
Time (ms)




feedback off

feedback on

feedback on (zoom)






- Vertical tune shift are a result of:
 - SPS transverse impedance and changing bunch length/intensity

BBQ-PLL based Q/Q' tracking

Since 2006: Collimator Imp. Q_x versus Full Gap Opening



- Tune resolution: $\Delta Q_{res} \approx 10^{-6} \dots 10^{-7}$

LHC Q/Q' system: 5 racks, 9 VME crates, 10 DAB front-ends:

- UA43-BY10 - support cavern left of IP4 [*CFV-UA43-BQB2*]
 - PLL-B2 (operation): Q/C Phase-Locked-Loop System Beam 2
 - connected to BQK.6R4 (aka. 'Q shaker')
 - FFT-B2 (operation): periodic acq., logging, fill-to-fill studies, Beam 2


- UA47-BY07 - support cavern right of IP4 [*CFV-UA47-BQB1*]
 - PLL-B1 (operation): as above but Beam 1
 - connected to BQK.6L4
 - FFT-B1 (operation) as above but Beam 1

- UA47-BY12 [*CFV-UA47-BQ → CFV-UA47-BQFFT?*]
 - FFT-B1, FFT-B2: on demand FFT spectra acquisition
 - connected to RF damper system
 - software + hardware (TTL) link to MKQA
 - N.B. can be also used for periodic acquisition
 - (BQSHT-B1/B2: 'Head-Tail' acquisition system)

- SX4-BY11 – surface building [*CFV-SX4-BQDEVB1, CFV-SX4-BQDEVB2*]
 - DEV-B1: LHC FFT/PLL/HT development system
 - DEV-B2: (Q: move to SPS? - “easier”/more available test-bed)

BBQ-PLL and -FFT Installation Overview

LHC Tune and Chromaticity Diag. & FB Control Systems, Ralph.Steinhausen@CERN.ch, 2008-03-06



PLL.B2
FFT1.B2

- BY10.UA43
- BPLH.A7L4.B2 (2c+m26)
- BPLH.B7L4.B2 (2c)
- BPLV.A5L4.B2 (2c+m26)
- BPLV.B4L4.B2 (2c)
- BY11.SX4 (2c+m48)
- BY08.UA47 (4c+m48)
- FFT1.B2, PLL.B2
- CFV-UA43-BQPLL

DEV.B1
DEV.B2

- BY11.SX4
- BY09.UA43 (4c+m48)
- BY10.UA43 (2c+m48)
- BY06.UA47 (2c+m48)
- BY07.UA47 (4c+m48)
- damp surface (4c)
- DEV.B1
- CFV-SX4-BQPLLB1
- DEV.B2
- CFV-SX4-BQPLLB2



PLL.B1
FFT1.B1

- BY07.UA47
- BPLH.A6R4.B1 (2c+m26)
- BPLH.B6R4.B1 (2c)
- BPLV.B6R4.B1 (2c+m26)
- BPLV.C6R4.B1 (2c)
- BY11.SX4 (4c+m48)
- damp tunnel (2c)
- FFT1.B1, PLL.B1
- CFV-UA47-BQPLL

FFT2.B1
FFT2.B2

- BY12.UA47
- BPLX.6R4.B1-H (2c+m26)
- BPLX.6R4.B1-V (2c)
- BPLX.6R4.B2-H (2c+m26)
- BPLX.6R4.B2-V (2c)
- BY10.SX4 (4c+m48)
- damp tunnel (4c)
- FFT2.B1, FFT2.B2
- CFV-UA47-BQ

Head-Tail and Schottky Installation Overview



HT.B1
HT.B2

BQS.B1
BQS.B2

BY12.UA47

BPLH.7R4.B1 (2c+m26)
BPLV.A6R4.B1 (2c)
BPLH.6R4.B2 (2c+m26)
BPLV.7R4.B2 (2c)

CFV-UA47-HT

BY13.UA47

BQSH.7R4.B1 (2c)
BQSV.5R4.B1 (2c)
BQSH.5R4.B2 (2c)
BQSV.7R4.B2 (2c)

BY12.SX4 (8c)


CFV-UA47-BQS

- CERN's Technical Network as backbone

- Switched network
 - no data collisions
 - no data loss
- double (triple) redundancy

- Core: “Enterasys X-Pedition 8600 Routers”

- 32 Gbits/s non-blocking, $3 \cdot 10^7$ packets/s
- 400 000 h MTBF
- hardware QoS
 - One queue dedicated to real-time feedback
 - ~ private network for the orbit feedback



- Routing delay ~ 13 μ s

- longest transmission delay (exp. verified) ~ 320 μ s

(500 bytes, IP5 -> Control room ~5 km)

- 20% due to infrastructure (router/switches)
- 80% due to traveling speed of light inside the optic fibre

- worst case max network jitter « targeted feedback frequency!

- The maximum latency between CCC and IR5
 - tail of distribution is given by front-end computer and its operating system

