



Real-Time Beam Control at the LHC

Ralph J. Steinhagen,
CERN, Beam Instrumentation Group

On behalf and special thanks to: LHC commissioning team,
M. Andersen, A. Boccardi, E. Calvo, R. Denz, M. Gasior,
L. Jensen, S. Jackson, R. Jones, Q. King, M. Lamont,
S. Page, J. Wenninger, and operations crew.

- Requirements: 'What was specified' vs. 'What was/is needed'
- Underlying Feedback Architecture




- Performance and Stability during LHC's First Year of Operation
 - Gretchenfrage: "Could or should LHC run without Feedbacks"
- Required Changes with respect to Initial Design

- Traditional requirements on beam stability...

... to keep the beam in the pipe!

- Increased stored intensity and energy:
 - up to 75 MJ@3.5 TeV in the beam (2011)
→ can quench all magnets/cause serious damage!
- Requirements depend on:
 1. Capability to control particle losses
 - Machine protection (MP) & Collimation
 - Quench prevention
 2. Commissioning and operational efficiency



Beam 3σ envel.
~ 1.8 mm @ 7 TeV

- FBs became a requirement for safe and reliable nominal LHC operation
 - implications on controller reliability, availability and system integration
- The main driving constraints:
 - ensuring collimator hierarchy \leftrightarrow minimising local bumps
 - $\Delta x \leq 25\text{-}50 \mu\text{m}$ at collimators \leftrightarrow constraints max. allowed oscillations
 - Decay- and snap-back of dipole's multipole components
 - Operating close to third order resonances
 - Keep beam excitation to a minimum: transverse emittance preservation



Expected Dynamic Perturbations vs. Requirements – or: Design Assumption vs. Operational Reality

- From Decay/Snap-back **expected dynamic perturbations**


	Orbit [σ]	Tune [$0.5 \cdot f_{rev}$]	Chroma. [units]	Energy [$\Delta p/p$]	Coupling [c]
Exp. Perturbations ('06):	~ 0.5	0.014	~ 70	$\pm 1.5e-4$	~0.01
Nom. Requirements:	± 0.15	± 0.001	2 ± 1	$\pm 1e-4$	$\ll 0.01$
Achieved Stability ('10):	~ 0.1	~ 0.001	± 2 (7)	~ $1e-5$	< 0.003

- Initial assumptions and plans (2006-2009):**
 - Chromaticity considered as most critical parameter
 - FB Priority list: **Chromaticity** → **Coupling/Tune** → Orbit → Energy
- What turned out to be needed operationally from 2009 → now:
 - **Tune** → **Tune** → ... → Orbit & Energy/Radial-Loop ... → $Q'(t)$ → ... → C^-
 - impressive $Q'(t)$, C^- and beta-beat stability and reproducibility



LHC Feedback Success has a long Pedigree: Years of Collaboration, Development and leveraged Experience

Real-Time Beam Control at the LHC, Ralph.Steinhagen@CERN.ch, New York, NY, 2011-03-30




2009 – the year we established collisions: Q/Q'- & Orbit FBs operational

Specific requirements fairly distributed → opted for **central global feedback system**

- One central controller (OFC + hot spare):
 - higher numerical load
 - higher network load (↔ 170 front-ends)
 - dependence of machine operation on single device
 - easier synchronisation between front-ends and FBs
 - flexible correction scheme changes and gain-scheduling
 - **efficient to handle cross-talk and coupling between FBs**

- Orbit-Feedback is the largest and most complex LHC feedback:
 - 1088 BPMs → 2176+ readings @ 25 Hz from 68 front-end computers
 - 530 correction dipole magnets/plane, distributed over ~50 front-end computers

- **Total >3500 devices involved ↔ more than half the LHC is controlled by FBs!**




Common Feedback/Feed-forward Control Layout

Control implementation split into two sub-systems:


- **Feedback Controller (OFC)** performing actual feedback controller logic
 - Simple streaming task (10% of total load)
 - Beam data quality checks and real-time filtering (80% of total load)
 - Server running Real-Time Linux OS with periodic constant load
 - multi-core, highly redundant – MTBF > 22 yrs (spec, 120 yrs meas.)
 - Technical Network as robust communication backbone

- **Service Unit:** Interface to high-level software control and interlock systems
 - Proxies user requests, handles asynchronous non-RT tasks





To avoid inherent Cross-Talk between FBs... ... Cascading between individual Feedbacks

- Main strategy: derive meas from FB control variable
 - Q'-tracker using ' $Q'_{raw} = Q_{meas} - Q_{trim}$ '
 - Sub. $\Delta p/p$ -mod. from Radial-Loop & Orbit-FB reference




further: $f_{BW}(PLL) \gg f_{BW}(Q') \geq f_{BW}(Q, C')$


- Initially: Truncated-SVD (set $\lambda_i^{-1} := 0$, for $i > N$)
 - not without issues: removed λ_i allowed local bumps creeping in (e.g. collimation)
- Regularised-SVD (Tikhonov/opt. Wiener filter with $\lambda_i^{-1} := \lambda_i / (\lambda_i^2 + \mu)$, $\mu > 0$)
 - more robust w.r.t. optics errors and mitigation of BPM noise/errors
 - allowed re-using same ORM for injection, ramp and 10+ squeeze steps



- Orbit feedback used routinely and mandatory for nominal beam





- Typical stability: 80 (20) μm rms. globally (arcs)
- Most perturbations due to Orbit-FB reference changes around experiments



- Orbit stability during physics $< 5 \mu\text{m}$ over 15 hours (Orbit-FB 'off')
 - new high-accuracy diode-based beam position monitor system: $\Delta x_{\text{res}} < 0.5 \mu\text{m}$

Earth Tides dominating Orbit Stability during Physics:

- Known effect from LEP → changes the machine circumference/energy




~ one week

– Testimony to LHC alignment and beam stability!




- Initial design assumption: no residual tune signatures on the beam (0 dB S/N)
 - Anticipated constant driving of the beam and – to limit the required excitation levels – the highly-sensitive BBQ system was developed

- Blessing/Curse after start-up:
 - BBQ turn-by-turn res. < 30 nm
 - 30+dB more sensitivity than other LHC systems (e.g. ADT: 1 μ m, BPM: 50 μ m)
 - Ever-present Q oscillations on the few 100 nm to μ m level



- Luxurious 30-40 dB S/N ratios enabled the passive monitoring, tracking and feedbacks without any additional excitation

- However: μm -level oscillations are incoherent “noise” from a Tune-PLL point of view
- Need to excite ~ 30 dB above this “noise” to recover “passive” FFT performance
 $\rightarrow 10\dots 100 \mu\text{m}$ oscillations vs. collimators $< 200 \mu\text{m}$
- Driving the beam with the present ample signals seemed to be inefficient/less robust
- PLL tracking in action:






Typical Q/Q'(t) Control Room View 2010 Statistics: Out of 191 Ramps...

Real-Time Beam Control at the LHC, Ralph.Steinhausen@CERN.ch, New York, NY, 2011-03-30

LHC - Fill#1574
2011-03-03 19:09:51

Q1 = .309714 Qx = .310523
Q2 = .319568 Qy = .318759
|C-| = .005410 E = 3500.0 GeV
Q'x = +16.2 ± .1
Q'y = +14.0 ± .3


Beam 1



LHC - Fill#1574
2011-03-03 19:09:51


Q1 = .310105 Qx = .310434
Q2 = .320267 Qy = .319938
|C-| = .003598 E = 3500.0 GeV
Q'x = ???
Q'y = +11.9 ± .4

Beam 2




- ... 155 ramps with > 99% transmission, 178 ramps with > 97% transmission
- ... only 12 ramps lost with beam (6 with Tune-FB during initial 3.5 TeV comm.)
- ... “if without FBs”: 83 crossings of 3rd, 4th or C- resonance, 157 exceeded $|\Delta Q| > 0.01$
- Impressive performance for the first year of operation and low-ish intensities:

Field measurements & Model





Today's circuit-by-circuit compensation:



- Model-based FF reduced expected 'Q'(t) swing' from 250 to less than 30 units
 - Low intensity beam survived these initial ramps
 - testimony to machine linearity and small machine impedance

- Feed-forward of $Q'(t)$ -Feedback signal for next fill turned out to be sufficient!
 - enforced by strict pre-cycling following physics, access or circuits 'off' ...



- Could/should LHC run without Feedbacks: – NO
 - 1 More than 50% of fills would have probably been lost without FBs
 - mostly during or after of changing the mode-of-operation
 - 2 Even with perfect feed-forward, FBs provide a robustness to operation by mitigating “unforeseen” or feed-down effects

However:

“Having a car brake or ESP/ABS system does not justify reckless driving!”

- Feedbacks may and do shadow systematic machine problems
 - reduces additional safety margin and increases the dependence on them
 - acceptable to quickly advance and as temporary mitigation solution
 - Logging of all feedback system actions used to monitor and identify potential problems, and to facilitate feed-forwarding

- Trims became de-facto standard to assess the FB and machine performance





Orbit-FB & Radial-Loop Trims (μrad)

Tune-FB trims

Q'(t)-FB trims
Energy (TeV)

β^* -squeeze

- Tunes kept stable to better than 10^{-3} for most part of the ramp and squeeze





- Feed-forward errors during snapback probably due to feed-down effects



Things that did not go according to the Cuning Plan...
Or: FBs are only as reliable as their Inputs they are based upon.



... fighting instabilities ...





- Presently compensated by data post-treatment \rightarrow max. orbit error $< \sim 70 \mu\text{m}$
 - Full temperature control of the crates are under investigation



Transverse Bunch-by-Bunch FB (ADT) & Tune Diagnostic – Conflicting Requirements


- Higher B-b-B FB gain implies also more meas. noise propagated onto beam...



- For the time being mitigated by reducing ADT gain when Tune-FB is needed
 - Under investigation: tune signal derived from ADT actuator control signal


Real-Time Beam Control at the LHC, Ralph.Steinhagen@CERN.ch, New York, NY, 2011-03-30

- Mains harmonics visible in spectrum and (minor) source of emittance growth



- adapted Q-detection filter to remove this → non issue for LHC Tune-FB

Mystery of the LHC Year 2010: Broad-band perturbation with shifting mean frequency



- Accepted Control-Room Jargon: of being “humped”
- Origin remains unknown but is less of an issue in now (2011)

- Feedbacks facilitated a fast commissioning and used de-facto during every ramp and squeeze with nominal beam
- Good overall performance with little transmission losses and minimal hick-ups related to Q/Q' instrumentation, diagnostics and Q/Q' & orbit feedbacks
- Impressive machine stability: Q'(t) and Coupling proved to very reproducible
 - enforced by strict pre-cycling following physics, access, circuits 'off', ...
 - fill-to-fill corrections appear to be sufficient for the time being
- With 2010 intensities no serious issues observed but need to revisit conflicting requirements for ADT and Q/Q' diagnostics once reaching the e-cloud barrier
- In the pipeline: beam-based gain-scheduling, polishing user-level interfaces...
- Success is not accident: LHC feedbacks are based on years of accumulated experience at CERN, BNL, FNAL, DESY, PSI, Diamond, Soleil and Triumf.



Thank You for your Attention!

- Snapshot of the day with removed mains harmonics

Tune Viewer - LHC - Continuous B2 (FFT1.B2)
Help

File Edit Run Timing Configure Fitter Settings

RBA: Incop User: LHC
RAMP
Continuous B2 (FFT1.B2)
LHC.OFSU
Tune-FB: ON

Info FFT DataSets Q' FB/Trim Orbit
Graph Mag H H II
ACQ# 0
Misc

Q-FPGA

Tune Measurements

CERN

LHC - B2 - Fill#1644.0
 2011-03-22 11:39:48
 RAW&FFT: 8192 turns@2.5Hz
 no excitation

Q1 = .279783	Qx = .281021
Q2 = .310160	Qy = .308922
C- = .012013	E = 888.8 GeV
Q'x = ???	
Q'y = ???	

Spawn TuneViewer Display

Comments:
no comment

Q

Q'

auto-save

LHC - B2 - fill #1644 - no comment - LHC_FFT1_B2 - 2011-03-22 11:39:48

Raw Spectrum

Filtered Spectrum/
Rejected Mains



LHC - B2 - fill #1644 - no comment - LHC_FFT1_B2 - 2011-03-22 11:39:48

11:40:28 - <2> Ulconf_FFT::UpdateSettings() - update read settings

- Nice and useful spectra with stable beams at 3.5 TeV:



Single Bunch: **Prontons vs Ions**

Single Bunch: **Prontons vs Ions**



Beam1V Slot 720 VS Beam1V Slot40


Beam2V Slot 699 VS Beam2V Slot40



Courtesy R. Jones, M. Favier

- Limited FB usability: reliability and achievable meas. bandwidth during ramp
→ for the time being limited to measurements during collisions


- Double- (triple-) redundant switched Gigabit Network: **no data collisions/loss**
 - Max transmission delay $\sim 320 \mu\text{s}$ (80% due to traveling speed of light)
- Total delays dominated by front-end:



- Communication un-critical: worst case jitter \ll feedback sampling frequency!**
 - Tested (short-term) operation up to 1 kHz (\leftrightarrow nominal 25 Hz)
 - in case of problems: HW-QoS queue dedicated \leftrightarrow private network for RT-FBs



Quirky side effect:

- Machine circumference changes are propagated via Q' also to the tune



- Probably the slowest high-precision Q' measurement in the World
 - Short-Term Tune-Stability of $\sim 10^{-6}$!
- However, stability during nominal physics operation is typically driven by impedance and beam-beam related effects.



- Analysed a total of 275 ramps, excluded most of early ramps in 2009





Peak-To-Peak Tune Trim and Tune Variations




■ Steady performance dominated snap-back...









Maximum Intensity and Transmission Loss during the Ramp Beam 1

- Most losses when switching mode of operation (single bunch → trains → ions)




- Limited or no correlation to transmission losses but beam size growth
- Biggest error: emittance growth estimates → Federico Roncarolo's talk





- Correlation between 0.5..0.7, biggest uncertainty derives from BSRT
→ use only linearity between fill-to-fill but not absolute values → F. Roncarolo

- Accepted Control-Room Jargon: being “humped”



- Partially mitigated by transverse feedback
- Origin of this perturbation remains unknown but is less of an issue in 2011

Residual overall Tune Stability in 2010 Out of 191 Ramps...





- 155 ramps with > 99% transmission
- 178 ramps with > 97% transmission
- 12 ramps lost (6 with Tune-FB during initial 3.5 TeV commissioning)
- Impressive performance for the first year of operation and low-ish intensities
 - caution: 1% loss of nominal beam may become more critical in 2011



Feed-Forward Back-Bone – Field-Description for LHC (FiDeL)

Example: b_3 – Compensation – Static Part

Based on magnet measurements:



Machine Optics Model

$$k_N = \frac{1}{B\rho} \frac{\partial B_x}{\partial y}$$

$$\frac{\partial B_y}{\partial x} = \frac{p \times k_n}{0.2998} \leftarrow p(t)$$

Transfer Function

$I(t)$